INTEGRATED DISPOSAL FACILITY CHANGE CONTROL LOG

Change Control Logs ensure that changes to this unit are performed in a methodical, controlled, coordinated, and transparent manner. Each unit addendum will have a "**Last Modification Date**" which represents the last date the portion of the unit has been modified. The "**Modification Number**" represents Ecology's method for tracking the different versions of the permit. This log will serve as an up-to-date record of modifications and version history of the unit.

Last modification to Integrated Disposal Facility September 1, 2022

Chapters	Last Modification Date	Modification Number
Unit-Specific Permit Conditions	02/01/2021	PCN-IDF-2020-06 (8C.2021.Q1)
1.0 Part A Form	02/01/2021	PCN-IDF-2020-06 (8C.2021.Q1)
2.0 Topographic Map Description	09/30/2014	
3.0 Waste Analysis Plan	06/30/2013	
4.0 Process Information	09/08/2020	PCN-IDF-2020-04 (8C.2020.Q3)
4A1 Phase I Critical Systems Design Report	09/08/2020	PCN-IDF-2020-04 (8C.2020.Q3)
4A2 Critical Systems Tables & Data Sheets	03/31/2008	
4A3 Critical Systems Design Drawings	09/01/2022	PCN-IDF-2022-01 (8C.2022.Q3)
4B Detailed Design Cell 1 Construction Quality Assurance Plan	04/09/2006	
4C Facility Response Action Plan	04/09/2006	
4D Construction Specifications (C-1). RPP-18489, Rev.1	09/08/2020	PCN-IDF-2020-04 (8C.2020.Q3)
C7 Leachate Monitoring Plan		
C7A Sampling and Analysis Plan for IDF Leachate		
C8 Sub-Surface Liquids Monitoring and Operations Plan		
C9 Infrastructure Construction Specification	09/08/2020	PCN-IDF-2020-04 (8C.2020.Q3)
5.0 Groundwater Monitoring	06/30/2010	
6.0 Procedures to Prevent Hazards	11/23/2020	PCN-IDF-2020-05 (8C.2020.Q4)
7.0 Reserved		
8.0 Personnel Training	09/30/2014	
9.0 Reserved		

10.0 Reserved		
11.0 Closure	09/30/2014	
11A Visual Sampling Plan Report <u>Documentation</u>		
12.0 Reserved		
13.0 Other Federal and State Laws	04/09/2006	
Addenda	Last Modification Date	Modification Number
Addenda Addendum J.1 Pre-Active Life Contingency Plan	Last Modification Date 11/23/2020	Modification Number PCN-IDF-2020-05 (8C.2020.Q4)



INTEGRATED DISPOSAL FACILITY PART III, OPERATING UNIT GROUP 11 UNIT-SPECIFIC PERMIT CONDITIONS CHANGE CONTROL LOG

Change Control Logs ensure that changes to this unit are performed in a methodical, controlled, coordinated, and transparent manner. Each unit addendum will have its own change control log with a modification history table. The "**Modification Number**" represents Ecology's method for tracking the different versions of the permit. This log will serve as an up to date record of modifications and version history of the unit.

Modification History Table

Modification Date	Modification Number
02/01/2021	PCN-IDF-2020-06 (8C.2021.Q1)
11/23/2020	PCN-IDF-2020-05 (8C.2020.Q4)
09/08/2020	PCN-IDF-2020-04 (8C.2020.Q3)
06/11/2020	PCN-IDF-2020-03 (8C.2020.Q2)
08/21/2018	PCN-IDF-2018-01 (8C.2018.Q3)
08/25/2016	8C.2016.Q2

This page intentionally left blank.



INTEGRATED DISPOSAL FACILITY PART III, OPERATING UNIT GROUP 11 UNIT-SPECIFIC PERMIT CONDITIONS



This page intentionally left blank.



1 2 3 4	PART	III, OPERATING UNIT GROUP 11, UNIT-SPECIFIC PERMIT CONDITIONS INTEGRATED DISPOSAL FACILITY
5 6	UNIT DESCR	<u>IPTION</u>
7 8 9 10 11 12	dangerous wast IDF disposal ce DWMU include transfer of leach	Disposal Facility (IDF) is permitted to operate two Leachate Collection System (LCS) to management units (DWMUs) as miscellaneous units to store leachate collected from the tells in accordance with Washington Administrative Code (WAC) 173-303-680. Each LCS as a Leachate Collection Unit (LCU) for leachate storage and ancillary equipment for the mate from the disposal cells. Ancillary equipment is comprised of the Crest Pad Building. fer Building, combined sump, and transfer piping.
13	This document	sets forth the operating conditions for IDF.
14	III.11.A	COMPLIANCE WITH APPROVED PERMIT
15 16 17 18	and Appendices Conditions III.1	shall comply with all requirements set forth in the IDF Permit Conditions, the Chapters is specified in Permit Condition III.11.A and the Amendments specified in Permit 11.B through III.11.I. All subsections, figures, and tables included in these portions are ess stated otherwise:
19	OPERATING	UNIT 11
20	Chapter 1.0	Part A Form, dated February 1, 2021
21	Chapter 2.0	Topographic Map Description, dated September 30, 2014
22	Chapter 3.0	Waste Analysis Plan, dated June 30, 2013
23	Chapter 4.0	Process Information, dated September 08, 2020
24 25	Appendix 4A1	Phase 1 Critical System Design Report (as applicable to critical systems), dated September 08, 2020
26	Appendix 4A2	Critical Systems Tables & Data Sheets
27	Appendix 4A3	Critical Systems Design Drawings
28	Appendix 4B	Detailed Design Cell 1 Construction Quality Assurance Plan, dated April 9, 2006
29	Appendix 4C	Facility Response Action Plan, dated April 9, 2006
30	Appendix 4D	Construction Specifications (C-1), (RPP-18489, Rev. 1), dated September 08, 2020
31	Appendix C7	Leachate Monitoring Plan
32	Appendix C7A	Sampling and Analysis Plan for IDF Leachate
33	Appendix C8	Sub-Surface Liquids Monitoring and Operations Plan
34 35	Appendix C9	Infrastructure Construction Specification (CHPRC-03953, Rev. 0), dated September 08, 2020
36	Chapter 5.0	Groundwater Monitoring, dated June 30, 2010
37	Chapter 6.0	Procedure to Prevent Hazards, dated November 23, 2020
38	Addendum J.1	Pre-Active Life Contingency Plan, dated November 23, 2020
39	Addendum J.2	Active Life Contingency Plan, dated March 31, 2016

- 1 Chapter 8.0 Personnel Training, dated September 30, 2014
- 2 Chapter 11.0 Closure, dated September 30, 2014
- 3 Appendix 11A Visual Sampling Plan Report Documentation
- 4 Chapter 13.0 Other Federal and State Laws, dated April 9, 2006
- 5 General and Standard Hanford Facility Resource Conservation and Recovery Act (RCRA) Permit,
- 6 WA7890008967 (Permit) conditions (Part I and Part II Conditions) applicable to the IDF are identified in
- 7 Permit Attachment 9, Permit Applicability Matrix.
- 8 **DEFINITIONS**
- 9 The following definitions are specific to the IDF.
- 10 LCS: miscellaneous unit also called LCU to store leachate collected from the IDF disposal cells and
- ancillary equipment for the transfer of leachate from the disposal cells, in accordance with WAC 173-303-11
- 12 680. IDF is permitted to operate two LCS DWMUs. Ancillary equipment is comprised of the Crest Pad
- 13 Building, Leachate Transfer Building, combined sump, and transfer piping.
- 14 Leak Detection System for the LCU: A leak detection system for the LCU allows leachate that may leak
- 15 through the primary liner to drain to a shallow sump at the center of the unit. Leachate will be then
- conveyed through pipe to the leak detection chamber in the combined sump located outside the perimeter 16
- 17 of the unit. Leachate collected in the combined sump is monitored by a moisture detector to determine
- 18 any leakage from the LCU primary liner.
- 19 **ACRONYMS**
- 20 The following acronyms are specific to the IDF unit:
- 21 Leachate Collection System
- LCU Leachate Collection Unit 22
- AMENDMENTS TO THE APPROVED PERMIT 23 III.11.B
- III.11.B.1 24 Portions of Permit Attachment 4, Hanford Emergency Management Plan that are not 25 made enforceable by inclusion in the applicability matrix for that document, are not made
- 26 enforceable by reference in this document.
- 27 III.11.B.2 Permittees must comply with all applicable portions of the Permit. The facility and 28 unit-specific recordkeeping requirements are distinguished in the General Information 29 Portion of the Permit, and are tied to the Permit conditions.
- 30 III.11.B.3 The scope of this Permit is restricted to the landfill construction and operation as 31
- necessary to dispose of: (1) Immobilized Low-Activity Waste (ILAW) from the Waste 32 Treatment Plant (WTP), and (2) the Demonstration Bulk Vitrification System (DBVS) 33 and IDF operational waste as identified in Chapter 4.0. Future expansion of the RCRA
- 34 trench, or disposal of other wastes not specified in this Permit, is prohibited unless 35 authorized via modification of this Permit.
- 36 III.11.B.4 In accordance with WAC 173-303-806(11)(d), this Permit shall be reviewed every five 37 (5) years after the effective date and modified, as necessary, in accordance with
- 38 WAC 173-303-830(3).
- 39 III.11.B.5 Inspection Requirements-Pre-Active Life Period and Active Life Period
- 40 The Permittees will comply with the inspection requirements specific to Chapter 6.0,
- "Procedures to Prevent Hazards," and Permit Condition II.O, in accordance with 41
- WAC 173-303-320, -395, -630, -640, -650, -665, and -680, incorporated by reference. 42

1 III.11.B.5.a The Permittees will conduct inspections of the IDF according to the following 2 requirements: 3 III.11.B.5.a.i Prior to the start of the Active Life of the IDF as defined in WAC 173-303-040, 4 according to Chapter 6.0, Table 6-2. 5 **III.11.B.5.a.ii** Following the start of the Active Life of the IDF as defined in WAC 173-303-040, 6 according to Chapter 6.0, Table 6-32A. 7 III.11.B.5.b The Permittees will remedy any problems revealed by inspections conducted pursuant to 8 Permit Condition III.11.B.5.a on a schedule, which prevents hazards to the public health 9 and the environment and as agreed to in writing, by the Department of Ecology 10 (Ecology). Where a hazard is imminent or has already occurred, remedial action must be taken immediately. 11 12 Reserved III.11.B.5.c 13 III.11.B.5.d Rainwater Management Prior to the start of the Active Life of the IDF, the Permittees will manage the discharge 14 III.11.B.5.e of such water in accordance with the pollution prevention and best management practices 15 16 required by State Waste Discharge Permit Number ST-4511. 17 III.11.B.5.e.i Management of Liquids Collected in the Leachate Collection and Removal System 18 (LCRS), Leak Detection System (LDS), and Secondary Leak Detection System (SLDS) 19 prior to the start of the Active Life of the IDF. 20 **III.11.B.5.e.ii** Permittees shall manage the liquid in the LCRS in a manner that does not allow the fluid head to exceed 30.5 cm above the flat 50-foot by 50-foot LCRS sump High Density 21 22 Polyethylene (HDPE) bottom liner, and the LCRS sump trough, except for storms that 23 exceed the 25-year, 24-hour storm event [WAC 173-303-665(2)(h)(ii)]. Liquid with a depth greater than 30.5 cm above the LCRS liner will be removed at the earliest 24 25 practicable time after detection (not to exceed 5 working days). 26 **III.11.B.5.e.iii** Accumulated liquid of pumpable quantities in the LDS and SLDS will be managed in a 27 manner that does not allow the fluid head to exceed 30.5 cm above the LDS liner or 28 SLDS liner [WAC 173-303-665(2)(h)(ii) and (iii)]. Liquid with a depth greater than 29 30.5 cm above a liner will be removed at the earliest practicable time after detection 30 (not to exceed 5 working days). III.11.B.5.e.iv The Permittees will use a flow meter to check if the amount of actual liquid pumped 31 32 corresponds to the amount accumulated in the LCU to verify the proper function of the 33 leachate collection and removal sump pumps with each use. The Permittees will 34 document in the IDF portion of the facility operating record appropriate quality 35 assurance/quality control requirements for selection and operation of the flow meter based on the required verification. In addition, the Permittees will evaluate the leachate 36 37 transfer lines for freeze and thaw damage when ambient conditions may cause such damage to occur. The Permittees will document the methods and criteria used for 38 39 purposes of this evaluation, along with an appropriate justification. 40 **III.11.B.5.e.v** The Permittee will inspect for liquids after significant rainfall events. 41 III.11.B.5.e.vi The Permittees will annually verify monitoring gauges and instruments are in current calibration; calibration will be performed annually or more frequently at intervals 42 43 suggested by the manufacturer (refer to Chapter 4.0, Section 4.3.7.4).

1 2	III.11.B.5.f	The Permittees will monitor liquids in the LCRS and LDS to ensure the action leakage rate (Chapter 4.0, Appendix 4A) is not exceeded.
3	III.11.B.5.g	Soil Stabilization
4 5		Prior to the first placement of waste in the IDF, the Permittee will apply soil stabilization materials as needed to prevent soil erosion in and around the landfill.
6	III.11.C	Design Requirements
7 8 9 10	III.11.C.1	IDF is designed in accordance with WAC 173-303-665 and WAC 173-303-640, -650, -665, and -680, and as described in Chapter 4.0. Design changes impacting IDF critical systems willshall be performed in accordance with Permit Conditions III.11.D.1.d.i and III.11.D.1.d.ii.
11 12 13 14	III.11.C.1.a	IDF Critical Systems include the following: the LCRS, LCUT, LDS, Liner System (LS), and closure cap. H-2 Drawings for the LCRS, LCUT, LDS, and LS are identified in Appendix 4A, Section 3 of this Permit. Drawings for the closure cap will be provided pursuant to Permit Condition III.11.C.1.c.
15 16 17		The Permittees shall construct and operate the IDF in accordance with all specifications contained in RPP-18489, Rev 0. Critical systems, as defined in the definitions section of the Site-wide RCRA Permit, are identified in Appendix 4A, Section 1 of this Permit.
18	III.11.C.1.b	Landfill Cap
19 20 21 22 23 24 25		At final closure of the landfill, the Permittees shall cover the landfill with a final cover (closure cap) designed and constructed [WAC 173-303-665(6), WAC 173-303-806(4)(h)] to: provide long-term minimization of migration of liquids through the closed landfill; function with minimum maintenance; promote drainage and minimize erosion or abrasion of the cover; accommodate settling and subsidence so that the cover's integrity is maintained; and have a permeability less than or equal to the permeability of any bottom liner system or natural subsoils present.
26	III.11.C.1.c	Compliance Schedule
27 28 29 30 31 32 33		Proposed conceptualized final cover design is presented in Chapter 11.0, Closure Requirements. Six months prior to start of construction of IDF landfill final cover (but no later than 6 months prior to acceptance of the last shipment of waste at the IDF), the Permittees shall submit IDF landfill final cover design, specifications and Construction Quality Assurance (CQA) Plan to Ecology for review and approval. No construction of the final cover may proceed until Ecology approval of the final design is given, through a permit modification.
34 35	III.11.C.1.d	The Permittees shall notify Ecology at least sixty (60) calendar days prior to the date it expects to begin closure of the IDF landfill in accordance with WAC 173-303-610(3)(c).
36	III.11.C.2	Design Reports
37	III.11.C.2.a	New Tank Design Assessment Report
38 39 40 41		Permittees shall generate a written report in accordance with WAC 173-303-640(3)(a), providing the results of the LCUT system design assessment. The report shall be reviewed and certified by an Independent Qualified Registered Professional Engineer (IQRPE) ¹ in accordance with WAC-173-303-810(13)(a).

¹"Independent Qualified Registered Professional Engineer," as used here and elsewhere with respect to Operating Unit Group 11, means a person who is licensed by the state of Washington, or a state which has reciprocity with the state of Washington as

1	III.11.C.2.b	Compliance Schedule
2 3 4		Permittees shall submit the LC <u>U</u> T design assessment report to Ecology along with the IQRPE certification, prior to construction of any part of the tank system including ancillary equipment.
5	III.11.D	CONSTRUCTION REQUIREMENTS
6	III.11.D.1	Construction Quality Assurance
7 8 9 10	III.11.D.1.a	Ecology shall provide field oversight during construction of critical systems. In cases where an Engineering Change Notice (ECN) and/or Non-Conformance Report (NCR) are required, Ecology and the Permittees shall follow steps for processing changes to the approved design per Permit Conditions III.11.D.1.d.i and III.11.D.1.d.ii.
11 12	III.11.D.1.b	Permittees shall implement the CQA plan (Appendix 4B of the Permit) during construction of IDF.
13 14 15 16 17 18	III.11.D.1.b.i	The Permittees will not receive waste in the IDF until the owner or operator has submitted to Ecology by certified mail or hand delivery a certification signed by the CQA officer that the approved CQA plan has been successfully carried out and that the unit meets the requirements of WAC 173-303-665(2)(h) or (j); and the procedure in WAC 173-303-810(14)(a) has been completed. Documentation supporting the CQA officer's certification shall be furnished to Ecology upon request.
19	III.11.D.1.c	Construction Inspection Reports
20 21 22 23 24 25 26 27		The Permittees willshall submit a report documenting the results of the LCSleachate tank installation inspection. This report must be prepared by an independent, qualified installation inspector or an professional IQRPE either of whom is trained and experienced in the proper installation of tank systems or components. The Permittees will remedy all discrepancies before the LCStank system is placed in use. This report willshall be submitted to Ecology at least ninety (90) days prior to the IDF operation and be included in the IDF-Hanford Facility Operating Record, IDF portion. [WAC 173-303-640(3)(h) and WAC 173-303-650(4)(a)].
28	III.11.D.1.d	ECN/NCR Process for Critical Systems
29 30		Portions of the following conditions for processing ECN and non-conformance reporting were extracted from and supersede Site-wide General Permit Condition II.L.
31	III.11.D.1.d.i	ECN for Critical Systems
32 33 34		During construction of the IDF, the Permittees shall formally document changes to the approved designs, plans, and specifications, identified in Appendices 4A, 4B, 4C, 4D, and C9 of this Permit, with an ECN.
35 36 37 38 39 40		The Permittees shall maintain all ECNs in the IDF unit-specific Operating Record and shall make them available to Ecology upon request or during the course of an inspection. The Permittees shall provide to Ecology copies of proposed ECNs affecting any critical system within five (5) working days of initiating the ECN. Identification of critical systems is included in Permit Condition III.11.C.1 and Appendix 4A of this Permit. Within five (5) working days, Ecology will review a proposed ECN modifying a critical

defined in Revised Code of Washington (RCW) 18.43.100, and who is not an employee of the owner or operator of the facility for which construction or modification certification is required. A qualified professional engineer is an engineer with expertise in the specific area for which a certification is given.

1 system and inform the Permittees whether the proposed ECN, when issued, will require a Class 1, 2, or 3 Permit modification. 2 3 III.11.D.1.d.ii Non-Conformance Reporting for Critical Systems 4 III.11.D.1.d.ii.a During construction of the IDF, the Permittees shall formally document with an 5 NCR, any work completed which does not meet or exceed the standards of the 6 approved design, plans and specifications, identified in Appendices 4A, 4B, 4C, 4D, 7 and C9 of this Permit. The Permittees shall maintain all NCRs in the IDF 8 unit-specific Operating Record and shall make them available to Ecology upon 9 request, or during the course of an inspection. 10 III.11.D.1.d.ii.b The Permittees shall provide copies of NCRs affecting any critical or regulated system to Ecology within five (5) working days after identification of the 11 12 non-conformance. Identification of critical systems is included in Permit Condition 13 III.11.C.1 and Appendix 4A of this Permit. Ecology will review a NCR affecting a 14 critical system and notify the Permittees within five (5) working days, in writing, 15 whether a Permit modification is required for any non-conformance, and whether 16 prior approval is required from Ecology before work proceeds, which affects the nonconforming item. 17 18 III.11.D.1.d.ii.c **As-Built Drawings** 19 Upon completing construction of IDF, the Permittees shall produce as-built drawings 20 of the project, which incorporate the design and construction modifications resulting 21 from all project ECNs and NCRs, as well as modifications made pursuant to 22 WAC 173-303-830. The Permittees shall place the drawings into the Operating 23 Record within twelve (12) months of completing construction. 24 III.11.D.2 The Permittees shall not reduce the minimum frequency of destructive testing less than 25 one test per 500 feet of seam, without prior approval in writing from Ecology. **GROUNDWATER AND GROUNDWATER MONITORING** 26 III.11.E 27 Groundwater shall be monitored in accordance with + and the provisions contained in the Ecology-approved facility "Groundwater Monitoring" (Chapter 5.0). All wells used to 28 29 monitor the groundwater beneath the unit shall be constructed in accordance with the provisions of WAC 173-160. 30 31 III.11.E.1 **Groundwater Monitoring Program** III.11.E.1.a 32 Prior to initial waste placement in the IDF landfill, the Permittees shall sample all 33 groundwater monitoring wells in the IDF network twice quarterly for one first year to 34 determine baseline conditions. For the first sampling event (and only the first), samples for each well will include all constituents in 40 Code of Federal Regulations (CFR) 264 35 Appendix IX. Thereafter, sampling will include only those constituents as specified in 36 37 Chapter 5.0, Table 5-2: Chromium (filtered and unfiltered the first year to compare 38 results), Specific conductance, Total organic carbon, Total organic halide, and pH. Other 39 constituents to be monitored but not statistically compared include alkalinity, anions, 40 Inductively Coupled Plasma metals, and turbidity. These will provide important 41 information on hydrogeologic characteristics of the aquifer and may provide indications of encroaching contaminants from other facilities not associated with IDF. 42


1 III.11.E.1.b After the baseline monitoring is completed, and data is analyzed, the Permittees and 2 Ecology shall assess revisions to Chapter 5.0, Table 5-2. Subsequent samples will be 3 collected annually and will include constituents listed in Table 5-2 as approved by 4 Ecology. All data analysis will employ Ecology approved statistical methods pursuant to 5 WAC 173-303-645. Changes to Chapter 5.0 will be subject to the permit modification 6 procedures under WAC 173-303-830. 7 III.11.E.1.c All constituents used as tracers to assess performance of the facility through computer 8 modeling should be sampled at least annually to validate modeling results. Groundwater 9 monitoring data and analytes to be monitored will be reviewed periodically as defined in 10 Chapter 5.0 of this Permit. 11 III.11.E.1.d Upon Ecology approval of the leachate monitoring plan, leachate monitoring and groundwater monitoring activities should be coordinated as approved by Ecology to form 12 13 an effective and efficient means of monitoring the performance of the IDF facility. 14 III.11.E.1.e Groundwater monitoring data shall be reported to Ecology annually by July 31. The 15 annual report shall include monitoring results for the 12-month period from January 1 16 through December 31. III.11.F LEACHATE COLLECTION COMPONENT MANAGEMENT 17 18 Permittees shall design, construct, and operate all leachate collection systems to minimize clogging during the Active Life and post-closure period. 19 20 III.11.F.1 Leachate Collection and Removal System 21 III.11.F.1.a At least 120 days prior to initial waste placement in the IDF, the Permittees shall submit a 22 leachate monitoring plan to Ecology for review, approval, and incorporation into the permit. Upon approval by Ecology, this plan will be incorporated into the Permit as a 23 Class ¹1 modification. The Permittees shall not accept waste into the IDF until the 24 25 requirements of the leachate monitoring plan have been incorporated into this Permit. 26 III.11.F.1.bIII.11.F.1.a Leachate in the LCRS (primary sump) shall-will be sampled and analyzed 27 monthly for the first year of operation of the facility and quarterly thereafter, as described in Appendix C7A, "Sampling and Analysis Plan for IDF Leachate (pursuant to 28 WAC 173 303 200)." Additionally, leachate from the LCUs willshall be sampled and 29 30 analyzed semi-annually to meet waste acceptance criteria at the receiving Treatment 31 Storage and Disposal Facility. 32 **III.11.F.1.c** III.11.F.1.b Permittees shall manage the leachate in the LCRS in a manner that does not 33 allow the fluid head to exceed 30.5 cm above the flat 50-foot by 50-foot LCRS sump 34 HDPE bottom liner except for rare storm events as discussed in Chapter 4.0, Section 35 4.23.6.1 and the LCRS sump trough [WAC 173-303-665(2)(h)(ii)]. Liquid with a depth greater than 30.5 cm above the SLDS liner will be removed at the earliest practicable 36 37 time after detection (not to exceed 5 working days). 38 III.11.F.1.dIII.11.F.1.c After initial waste placement, Permittees shall manage all leachate from the 39 permitted cell as dangerous waste (designated with Dangerous Waste Number F039) in 40 accordance with WAC 173-303. 41 III.11.F.2 Monitoring and Management of LDS (LDS/Secondary Sump) 42 III.11.F.2.a Permittees shall manage the leachate in the LDS in a manner that does not allow the fluid 43 head to exceed 30.5 cm above the LDS liner [WAC 173-303-665(2)(h)(ii)].

1 2 3 4	III.11.F.2.b	Permittees shall monitor and record leachate removal for comparison to the Action Leakage Rate (ALR) as described in Appendix 4C, <u>"Facility Response Action Plan."</u> If the leachate flow rate in the LDS exceeds the ALR, the Permittees shall implement the Ecology approved Response Action Plan (Appendix 4C).
5 6	III.11.F.2.c	Leachate from the LDS (secondary sump) shall be sampled semi-annually if a pumpable quantity of leachate is available for sampling.
7 8 9 10 11	III.11.F.2.d	Accumulated liquid of pumpable quantities in the LDS will be managed in a manner that does not allow the fluid head to exceed 30.5 cm above the LDS liner [WAC 173-303-665(2)(h)(ii) and (iii)]. Liquid with a depth greater than 30.5 cm above the LDS liner will be removed at the earliest practicable time after detection (not to exceed 5 working days).
12	III.11.F.3	Monitoring and Management of the SLDS
13 14 15 16 17 18	III.11.F.3.a	At least 180 days prior to initial waste placement, the Permittees shall submit to Ecology for approval a Sub-Surface Liquids Monitoring and Operations Plan (SLMOP) for the SLDS to include the following: monitoring frequency, pressure transducer configuration, liquid collection and storage processes, sampling and analysis and response actions. The SLMOP shall be approved by Ecology prior to placement of waste in the IDF, and incorporated into the Permit as a Class ¹ 1 modification.
19 20	III.11.F.3.b	Permittees shall monitor and manage the SLDS (tertiary sump) pursuant to the approved SLMOP.
21 22 23 24 25	III.11.F.3.c	Accumulated liquid of pumpable quantities in the SLDS will be managed in a manner that does not allow the fluid head to exceed 30.5 cm above the SLDS liner [WAC 173-303-665(2)(h)(ii) and (iii)]. Liquid with a depth greater than 30.5 cm above the SLDS liner will be removed at the earliest practicable time after detection (not to exceed 5 working days).
26 27	III.11.F.3.d	After initial waste placement, Permittees shall manage all leachate from the permitted cell as dangerous waste in accordance with WAC 173-303.
28	III.11.F.4	Monitoring and Management of the LCS
29 30	III.11.F.4.a	The Permittees will operate and maintain the physical structure of the LCS as documented in the applicable sections of Chapter 4.0.
31 32 33 34 35 36	III.11.F.4.b	The Permittees will develop a schedule for conducting Integrity Assessments on the LCUs before acceptance of waste [WAC 173-303-640(3)]. The schedule will meet the requirements of Chapter 4.0. The Permittees will maintain a copy of the schedule in the Hanford Facility Operating Record, IDF portion. Periodic integrity assessments will be conducted according to the schedule and results documented in the Hanford Facility Operating Record, IDF portion.
37 38 39 40 41	III.11.F.4.c	If there is an unexpected change in liquid level or observed evidence of a leak from the LCU and/or ancillary equipment, resulting in a spill into the environment, the Permittees must follow the required actions detailed in the applicable section of Chapter 4.0, "Process Information," in accordance with WAC 173-303-650(5) and WAC 173-303-640(7).
42 43 44 45	III.11.F.4.d	Permittees will monitor and record leachate removal from the combined sump for comparison to the ALR as described in Appendix 4C, "Facility Response Action Plan." If the leachate leakage rate in a combined sump exceeds the ALR, the Permittees will implement the Ecology approved response action plan.

1 III.11.F.4.e If the bottom liners are replaced or modified, then the Permittees will install a low 2 hydraulic conductivity geosynthetic clay liner under the bottom geomembrane liner, or an 3 equivalent material. 4 III.11.F.4.f No later than six (6) months prior to acceptance of the last shipment of waste at the IDF, 5 the Permittees will submit a permit modification request to Ecology to add Sampling and 6 Analysis Plan to support clean closure of the LCS DWMUs. The Sampling and Analysis 7 Plan will include the closure performance standards in accordance with WAC 173-303-8 610(2), as described in Chapter 11.0. 9 III.11.F.4.g The Permittees will monitor liquids in the LCS to ensure the action leakage rate (Appendix 4C) is not exceeded. 10 III.11.G **CONSTRUCTION WATER MANAGEMENT** 11 12 III.11.G.1 During construction, it is anticipated that liquids will accumulate on top of all liners and 13 sumps. Permittees shall manage the construction wastewater in accordance with State 14 Waste Discharge Permit ST-4511. 15 III.11.G.2 Liquid accumulation within the LCRS, LDS, and SLDS prior to initial waste placement will be considered construction wastewater (i.e., not leachate). 16 LANDFILL LINER INTEGRITY MANAGEMENT & LANDFILL OPERATIONS III.11.H 17 18 III.11.H.1 Permittees shall design, construct, and operate the landfill in a manner to protect the 19 liners from becoming damaged. Temperature: waste packages with elevated temperatures 20 shall be evaluated and managed in a manner to maintain the primary (upper) liner below 21 the design basis temperature for the liner (e.g., 160°F). Weight: waste, fill material and 22 closure cover shall be placed in a manner that does not exceed the allowable load bearing 23 capacity of the liner (weight per area 13,000 lb/ft²). Puncture: at least 3 feet of clean 24 backfill material shall be placed as an operations layer over the leachate collection and 25 removal system to protect the system from puncture damage. 26 III.11.H.1.a All equipment used for construction and operations inside of the IDF shall meet the 27 weight limitation as specified in Permit Condition III.11.H.1. Only equipment that can be adequately supported by the operations layer as specified in Permit Condition III.11.H.1 28 29 (e.g., will not have the potential to puncture the liner) shall be used inside of the IDF. All 30 equipment used for construction and operations outside of the IDF shall not damage the berms. Changes to any equipment will follow the process established by Condition II.R 31 32 of the Site-wide Permit. Within 120 days from the effective date for the permit, a process for demonstrating compliance with this condition shall be submitted for review by 33 34 Ecology. This process will be incorporated into appropriate IDF operating procedures 35 prior to IDF operations. 36 III.11.H.2 The Permittees shall construct berms and ditches to prevent run-on and runoff in 37 accordance with the requirements of Chapter 4.0, Section 4.23.8 of the IDF portion of 38 this Permit. Before the first placement of waste in the IDF, the Permittees shall submit to 39 Ecology a final grading and topographical map on a scale sufficient to identify berms and 40 ditches used to control run-on and runoff. Upon approval, Ecology will incorporate these maps into the permit as a Class ¹1 modification. 41 42 III.11.H.3 The Permittees shall operate the RCRA IDF Cell (Cell 1) in accordance with 43 WAC 173-303-665(2) and the operating practices described in Chapters 3.0, 4.0, 6.0, 8.0, 44 Addendum J.1, Addendum J.2, and Appendix 4A, Section 1, subsection 7, except as 45 otherwise specified in this Permit.

1 III.11.H.4 The Permittees shall maintain a permanent and accurate record of the three-dimensional 2 location of each waste type, based on grid coordinates, within the RCRA IDF Cell 3 (Cell 1) in accordance with WAC 173-303-665(5). 4 III.11.I WASTE ACCEPTANCE CRITERIA 5 The only acceptable waste form approved for disposal at the RCRA cell of IDF are IDF 6 operational waste, ILAW in glass form from the WTP Low-Activity Waste (LAW) 7 Vitrification Facility and ILAW from the Bulk Vitrification Research Demonstration and 8 Development Facility (up to 50 boxes). Specifics about waste acceptance criteria for each 9 of these wastes are detailed below. 10 No other waste forms may be disposed at the RCRA cell of IDF unless authorized via a final permit modification decision. Requests for Permit modifications must be 11 12 accompanied by an analysis adequate for Ecology to comply with State Environmental 13 Policy Act (SEPA), as well as by a risk assessment and groundwater modeling to show 14 the environmental impact. Permit Condition III.11.I.5 outlines the process by which 15 waste sources in the IDF are modeled in an ongoing risk budget and a groundwater 16 impact analysis. III.11.I.1 Six months prior to IDF operations Permittees shall submit to Ecology for review, 17 18 approval, and incorporation into the permit, all waste acceptance criteria to address, at a 19 minimum, the following: physical/chemical criteria, liquids and liquid containing waste, 20 land disposal restriction treatment standards and prohibitions, compatibility of waste with 21 liner, gas generation, packaging, handling of packages, minimization of subsidence. 22 III.11.I.1.a All containers/packages shall meet void space requirements pursuant to 23 WAC 173-303-665(12). 24 III.11.I.1.b Compliance Schedule 25 III.11.1.b.i Six months prior to IDF operations, the Permittees shall submit to Ecology for review, approval, and incorporation into the Permit any necessary modifications to the IDF 26 27 "Waste Analysis Plan" (Chapters 3.0 of the IDF portion of this Permit). 28 III.11.I.2 ILAW Waste Acceptance Criteria 29 The only ILAW forms acceptable for disposal at IDF are: (1) approved glass canisters 30 that are produced in accordance with the terms, conditions, and requirements of the WTP 31 portion of the Permit, and (2) the 50 bulk vitrification test boxes as specified in the 32 DBVS test plans. 33 To assure protection of human health and the environment, it is necessary that the 34 appropriate quality of glass be disposed at IDF. The Land Disposal Restrictions (LDR) Treatment Standard for eight metals (arsenic, barium, cadmium, chromium, lead, 35 mercury, selenium and silver), when associated with High-Level Waste, is High Level 36 37 VIT (HLVIT) (40 CFR 268). Because these metals are constituents in the Hanford Tanks Waste, the LDR standard for ILAW disposed to IDF is HLVIT. 38 39 For any ILAW glass form(s) that the United States Department of Energy (DOE) intends 40 to dispose of in IDF, DOE will provide to Ecology for review, an ILAW Waste Form Technical Requirements Document (IWTRD). The IWTRD will contain: 41

1 III.11.I.2.a WTP ILAW Waste Acceptance Criteria 2 III.11.I.2.a.i A description of each specific glass formulation that DOE intends to use including a basis 3 for why each specific formulation is proposed for use, which specific tank wastes the 4 glass formulation is proposed for use with, the characteristics of the glass that are key to 5 satisfactory performance (e.g., Vapor Hydration Test [VHT], Product Consistency Test 6 [PCT], and Toxicity Characteristic Leaching Procedure [TCLP] and/or other approved 7 performance testing methodologies that the parties agree are appropriate and necessary), 8 the range in key characteristics anticipated if the specific glass formulation is produced 9 on a production basis with tank waste, and the factors that DOE must protect against in 10 producing the glass to ensure the intended glass characteristics will exist in the actual ILAW. 11 12 III.11.I.2.a.ii A performance assessment that provides a reasonable basis for assurance that each glass formulation will, once disposed of in IDF in combination with the other waste volumes 13 14 and waste forms planned for disposal at the entire IDF, be adequately protective of human health and the environment; and will not violate or be projected to violate all 15 16 applicable state and federal laws, regulations and environmental standards. Within 60 days of a request by Ecology, the Permittees shall provide a separate model run 17 using Ecology's assumptions and model input. 18 19 III.11.I.2.a.iii A description of production processes including management controls and quality 20 assurance/quality control requirements that assure that glass produced for each 21 formulation will perform in a reasonably similar manner to the waste form assumed in the 22 performance assessment for that formulation. 23 The Permittees shall update the IWTRD consistent with the above requirements for review by Ecology consistent with their respective roles and authority as provided under 24 the Tri-Party Agreement (TPA). Ecology comments shall be dispositioned through the 25 Review Comment Record (RCR) process and will be reflected in further modeling to 26 modify the IDF ILAW Chapter 3.0, "Waste Analysis Plan" as appropriate. 27 28 The initial IWTRD contained glass formulation data as required by Permit Condition 29 III.11.I.2.a.i, and was submitted on December 18, 2006 (AR Accession # 0906020182). 30 The performance assessment required by Permit Condition III.11.I.2.a.ii, and the quality 31 assurance/quality control requirements process required by Permit Condition 32 III.11.I.2.a.iii shall be submitted for Ecology review as soon as possible after issuance of the Final Tank Closure and Waste Management Environment Impact Statement (EIS) and 33 34 receipt of underlying codes and data packages, and at least 180 days prior to the date DOE expects to receive waste at IDF. At a minimum, the Permittees shall submit updates 35 36 to the IWTRD to Ecology every five years or more frequently with the next one due June 30, 2015, if any of the following conditions exist: 37 38 The Permittees submits a permit modification request allowing additional waste forms to be disposed of at IDF. 39 40 The WTP or other vitrification facility change their glass formulations from those 41 previously included in the IWTRD. 42 An unanticipated event or condition occurs that Ecology determines would 43 warrant an update to the IWTRD. 44 III.11.I.2.a.iv The Permittees shall not dispose of any WTP ILAW not described and evaluated in the 45 IWTRD.



1 III.11.I.5.a.ii If these modeling efforts indicate results within 75% of a performance standard 2 (including but not limited to federal drinking water standards [40 CFR 141 and 3 40 CFR 143]), Ecology and the Permittees will meet to discuss mitigation measures or 4 modified waste acceptance criteria for specific waste forms. 5 III.11.I.5.a.iii When considering all the waste forms to be disposed of in IDF, the Permittees shall not 6 dispose of any waste that will result (through forward-looking modeling or in real 7 groundwater concentrations data) in a violation of any state or federal regulatory limit, 8 specifically including but not limited to drinking water standards for any constituent as 9 defined in 40 CFR 141 and 40 CFR 143. 10 III.11.I.6 The Permittees shall not dispose of any waste that is not in compliance with state and 11 federal requirements as identified in Chapter 13.0. III.11.I.6.a 12 In accordance with DOE's authority under the Atomic Energy Act of 1954, as amended and other applicable law, prior to disposing of any mixed ILAW in the IDF, DOE will 13 14 certify to the State of Washington that it has determined that such ILAW is not 15 High-Level Waste and meets the criteria and requirements outlined in DOE's 16 consultation with the U.S. Nuclear Regulatory Commission (USNRC) beginning in 1993 17 (Letter from R.M. Bernero, USNRC to J. Lytle, DOE, dated March 2, 1993; Letter from J. Kinzer, DOE, to C. J. Paperiello, USNRC, Classification of Hanford Low-Activity 18 19 Tank Waste Fraction, dated March 7, 1996; and Letter from C.J. Paperiello, USNRC, to 20 J. Kinzer, DOE, Classification of Hanford Low-Activity Tank Waste Fraction, dated 21 June 9, 1997). While the requirement to provide such certification is an enforceable 22 obligation of this Permit, the provision of such certification does not convey, or purport 23 to convey, authority to Ecology to regulate the radioactive hazards of the waste under this 24 permit. 25 III.11.I.7 IDF Operational Waste Acceptance Criteria 26 III.11.I.7.a IDF operational activities (including decontamination, cleanup, and maintenance) will 27 generate a small amount of waste. Waste that can meet IDF waste acceptance without 28 treatment will be disposed of at the IDF. All other IDF operational waste will be managed 29 pursuant to WAC 173-303-200. 30

This page intentionally left blank.

